

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber 5 pg 80

Oscoda (County) Located In: Corner Code #
1. Public Land Survey T 27N R 2E A-5
T 27N R 1E M-5
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

STATE OF MICHIGAN
OSCODA COUNTY
FILED
9 AUG 2000 3:22:04 PM
PATSY J. PETERS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (5,5) is shaded.

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Corner common to Sections 12 and 13, T27N, R1E and Sections 7 and 18, T27N, R2E
G.L.O.-1839 Lewis Clason GLO 1839 W. Coon, DS 1968 Consumers Power Co. H.W. Dorcey LCRC L1, P116 Apr. 1973
Mon.-post Mon - Post Mon - Not given N. C. Caldwell, PS #12018
Wit: 8" Spr. Pine N55°E 125 lks Wit: 4" Spr. Pine N23°E 278 1/2 lks Wit: None given Mon - Fd. Consumers
5" Spr. Pine N8°W 89 lks 4" Dwarf Oak S60°E 314 lks co. "T" iron; replaced with
Std. County Corner.
Wit: DNR post S45°E 47.0
DNR post N45°W 47.0
DNR route sign N80°W 39.6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner common to Sections 12 and 13, T27N, R1E and Sections 7 and 18, T27N, R2E
Found Standard County Corner in Centerline of Town Line Road and Helmer Lake Road; found DNR marker Post N45°W 47.0; found DNR route sign N80°W 39.6
Accepted Standard County Corner as the best available evidence of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner common to Sections 12 and 13, T27N, R1E and Sections 7 and 18, T27N, R2E
Mon - Standard County Monument.
Wit: Nail N. side 8" J. Pine N50°W 40.65
Nail S. side 6" J. Pine N15°W 81.22
Nail N. side 6" J. Pine N75°E 51.55
Nail N. side 6" J. Pine S40°E 72.62

APPROVED
County Monumentation
Peer Review Group
NCC
27 JULY 00



Signed by [Signature]
Surveyor's Michigan License No. 31600

Date July 10, 2000