

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 p951

For corners in

OSCODA Located In: ELMER Corner Code # A-9  
(County)

- 1. Public Land Survey T<sup>27N</sup> R<sup>2E</sup> A-9  
T<sup>27N</sup> R<sup>1E</sup> 1159  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

15 SEP 1999 9:32:39 AM

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, FREDERICK J. KING, in a field survey on June 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 - CORNER COMMON TO SECTIONS 19 & 30 (27-2) AND 24 & 25 (27-1)
- Dec. - 1839 - Lewis Clason, Dep. Sur. - Set Orig Post \*S76\*W-14 lks(9.24')-11" Aspen \* N37\*W-46 lks(30.36')-14" Y.Pine
- Oct. 1887 - Re-Set by John Randall Co Sur. - S76 W-14 lks (9.24') 11" Aspen \* N37 W-46 lks (30.36') 14" Y. Pine
- Oct. 1943 - Sur by G.D. Henning PS#2240 - Fnd Co<sup>g</sup> perpetuated from Original US Survey (Sleigh Shoe Fnd)  
N45°E-61.1' -8" N. Pine(Old BT) S66 W-84.5'-10" N. Pine (On File at Oscoda Co Reg Deeds)
- UNKNOWN - Map obtained from DNR, Indicates that Marcus Schaff Fnd Cor. - No Cor Desc. - No Wit.
- Jan 1970 - Act 132 by N.C. Caldwell PS#12018 - Indicates Cor Used - (Rec Bk T27N-R1E)
- Nov. 1972 - Act 132 by N.C. Caldwell PS#12018 - Fnd Rec. Sleigh Shoe (Rec L.1, Pg.250) - Same Wit as 1943 Henning Sur.
- July 1974 - Act 132 by N.C. Caldwell PS#12018 - Shows Cor Used - No Desc.- No Wit. (Rec. L.4, Pg. 536)
- Jan 1981 - Act 132 by F.J. King PS#25852 - Shows Cor Used - No Desc. - No Wit (Not Rec.)
- April 1987 - Act 132 by F.J. King PS#25852 - Fnd Std Co cor. - No Wit (Rec. L.4, Pg. 322)
- April 1997 - Act 132 by L.G. Beauregard PS#18654 - Fnd Std Co Cor - (Rec L. 197, Pg. 3093 \* N45°E-61.0' - 15" Nor (R)  
S45°E-46.52' - 1/2 I&C \* S45 W-44.45' - P. Pole \* N20 W-89.50' - 7" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9 - CORNER COMMON TO SECTIONS 19 & 30 (27-2) AND 24 & 25 (27-1)
- Fnd Rec. Co. Cor - N45°E-61-0'-15" N. Pine (R)
- S45°E-46.52' - Fnd 1/2" I&C
- S45°W-44.45'-P. Pole
- N20°W-89.50' - 7" Cedar

APPROVED

County Remonumentation  
Peer Review Group

7 SEPT 99  
NCC

THIS CORNER APPROVED BY OSCODA COUNTY PEER REVIEW ON JULY 9, 1999 AS A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 - CORNER COMMON TO SECTIONS 19 & 30 (27-2) AND 24 & 25 (27-1)
- RECORD STANDARD COUNTY CORNER
- N45°E - 61.00' - Fnd S&T #18654 on NW side 20" Norway
- S45°E - 46.52' - Fnd 1/2" I&C #18654 with USFS Post Alongside
- S45°W - 44.45' - Fnd S&T #18654 on NW side P. Pole #L54-155-32
- N20°W - 89.50' - Fnd S&T #18654 on E side 7" Cedar
- Corner is In C.L. of N-S Gravel Rd. (Townline Rd.)
- Corner is In C.L. of E-W Gravel Rd. (Kneeland Rd.)



Signed by Frederick J. King  
Surveyor's Michigan License No. 25852

Date August 28, 1999