

SEP 17 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg 53

For corners in

OSCODA _____ (County)	Located In: ELMER	Corner Code #
1. Public Land Survey	T 27N R 2E <del>T 21N R 1E</del>	A-11 ✓ M-11
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

15 SEP 1999 9:34:38 AM

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, FREDERICK J. KING, in a field survey on June 4, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-11 - CORNER COMMON TO SECTIONS 30 & 31 (27-2) AND 25 & 36 (27-1)  
Dec. 1839 - Lewis Clason, Dep. Sur. - Set Orig Post \* S58°W-74 lks(48.84')-16" Spruce \* N76°W-31 lks(20.46')-8" Spruce
- Oct. 1887 - Re-Set by John Randall Co Sur - S58°W-74 lks (48.84') 16" Spr. Pine \* N76°W-31 lks (20.46') 8" Spr Pine
- Oct. 1943 - Sur. by G.D. Henning, PS#2240 - Fnd Car Spring in center of Rd. - Varified by remains of Orig. US B.T.'s  
S30°E-58.5'-12" J. Pine \* S36°W-44.6'- 5" J. Pine
- Jan. 1981 - Act 132 by F.J. King PS#25852 - Fnd Std CO Cor. N20°E-58.0'-10" Oak \* S80°E-33.3'-15" Oak  
S30°E-66.9'-8" Pop \* West - 33.3' DNR Post -(Not Recorded)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 - CORNER COMMON TO SECTIONS 30 & 31 (27-2) AND 25 & 36 (27-1)

- Fnd 5/8 Iron - No Cap - S30°E-58.5' - Dead J. Pine (BT)
- Fnd All Jan 1981 F.J. King Witnesses

APPROVED

County Remonumentation  
Peer Review Group

1 SEPT 99  
NCC

THIS CORNER APPROVED BY OSCODA COUNTY PEER REVIEW, ON JULY 9, 1999, AS A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 - CORNER COMMON TO SECTIONS 30 & 31 (27-2) AND 25 & 36 (27-1)

- Plaged Oscoda County Re-mon Cap on Fnd 5/8' Iron
- N20°E - 57.94' (R-58.0') Set S&T above fnd Spk on E side 12" Oak
- S80°E - 33.3' - 15" Oak (Now Dead - 81 Wlt)
- S80°E - 37.65' - Set S&T on N side 10" Maple
- S30°E - 58.5' - Stump (81 - Wlt)
- S10°E - 66.91' - Set S&T on E side P. Pole #LS-46
- WEST - 33.20' (R-33.3') Set S&T above fnd Spk on S side USFS Post
- N65°W - 43.85' - Set S&T on NE side 6" Oak \*\* Corner is - 2' W of C.L. of N-S Gravel Rd. (Townline Rd.)



Signed by Frederick J. King  
Surveyor's Michigan License No. 25852

Date August 28, 1999