

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located in:

Corner Code #

Liber 5 pg. 82

- 1. Public Land Survey T 27N R 2E B-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

Closing N 1/4 corner Section 6, T27N, R2E

This corner not set by GLO 1968 DNR by K. Ostling of Section 31, T28N, R2W does not indicate that corner was reestablished, however, 1982 survey by K. Ostling state corner set in previous survey of Section 31, T28N, R2W

1995 R. Mitchell, PS
Mon - Set 1/2" Bar and Cap by single proportional measure
Wit: Fd. Spike in S. side 14" Oak N62°E 38.81
Fd. Spike in W. side 12" Oak S30°W 26.53
Fd. Spike in S. side 14" J. Pine S83°E 24.32
Fd. Spike in W. side 12" Oak S10°E 8.14

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Closing N 1/4 corner Section 6, T27N, R2E

Found 1/2" bar; found nail W. side 17" B. Oak S12°E 8.25; found Spike N. side 13" Jackpine S38°W 12.58; found spike in S. side 13" J. Pine S78°E 24.32; found Nail SE side 17" B. Oak N62°E 38.81; B-13 is West 1.35. Accepted 1/2" bar as a careful and faithful reestablishment of the position of the Government Corner. Replaced 1/2" bar with 5/8"x34" Steel Rebar with Standard Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Closing N 1/4 corner Section 6, T27N, R2E

Mon - Standard Oscoda County Monument
Wit: Nail W. side 9" B. Oak S12°E 8.25
Spike N. side 13" J. Pine S38°W 12.58
Spike S. side 13" J. Pine S78°E 24.32
Nail SE. side 17" B. Oak N62°E 38.81

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date July 10, 2000

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		8		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													