

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg. 83

For corners in

Oscoda
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
OSCOBA COUNTY
FILED

9 AUG 2000 3:25:11 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 27N R 2E B-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3		•											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

¼ corner common to Section 6 and 7, T27N, R2E

G.L.O - 1839 W. R. Coon, DS
Mon - Post
Wit: 6" Spr. Pine S38°E 11 lks
4" Spr. Pine N40°W 58 lks

1883 J. Randall, CS
Mon - Identified by US BTs
Wit: 14" Y. Pine N8 ½°E 135.5 lks
8" S. Pine S33°W 64 lks

1982 LCRC L1, P273 K. Ostling #10068
Mon - Set DNR Monument by proportional measure between Section corners.
Wit: 6" B. Oak S04°E 22.4
4" Jackpine S26°W 16.8 Set SPK W SD 18" Poplar N10E 43.28
Post with tag South 15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

¼ corner common to Section 6 and 7, T27N, R2E

Found Standard DNR Pipe & cap; found 6" B. Oak S04°E 22.4; found 4" Jackpine S26°W 16.8; found Post with tag South 15 (measures 14.23 to face). Accepted DNR monument as a careful and faithful reestablishment of the position of the Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

¼ corner common to Section 6 and 7, T27N, R2E

Mon - Standard DNR Monument.
Wit: Nail W. side 9" J. Pine S26°W 16.95
Nail E. side 8" B. Oak S04°E 22.39
Nail E. side 4" J. Pine N03°W 28.05
Nail W. side 12" J. Pine S45°E 35.96

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00



Signed by [Signature]
Surveyor's Michigan License No. 31600

Date July 10, 2000