DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)

Liber 5 pg 84

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:26:41 PM

PATSY J. PETERS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

		Located In:	Corner Code #
1. Public Land Survey		T 27N R 2E	B-5
		T ____ R ____	
		T ____ R ____	
		T ____ R ____	
2. Property Controlling	S ____	T ____ R ____	
in Section	S ____	T ____ R ____	
3. Miscellaneous	S ____	T ____ R ____	
Property in Sec.	S ____	T ____ R ____	

4. Lot No. _____ , Recorded Plat _____
5. Private Claims_____



I, Marvin E. Myers , in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

¼ corner common to Section 7 and 18, T27N, R2E

G.L.O - 1839 W. R. Coon, DS
Mon - Post
Wit: 4" Dwarf Oak S29°E 98 lks
4" Dwarf Oak N72°E 135 lks

circa 1930's M. Schaaf
Mon – Found or established *or replaced*

1968 Consumers Power co.
H. W. Dorcey
Mon – Not given
Wit: None given

1973 LCRC L1, P117 N. C. Caldwell #12018
Mon –Set Standard County Corner by Single proportional measure.
Wit: 10" N. Pine N78°W 32.6
6" N. Pine N06°E 18.1
14" J. Pine S78°E 32.8
Corner is 35'± North of E-W Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

¼ corner common to Section 7 and 18, T27N, R2E

Found Standard County Corner 35'± North of E-W Road; found nail in N. side 14" Norway 32.65. Accepted Standard County Corner monument as a careful and faithful reestablishment of the position of the Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

¼ corner common to Section 7 and 18, T27N, R2E

Mon – Standard Oscoda County Monument.
Wit: Nail N. side 14" Norway 32.65
Nail E. side 4" J. Pine N05°W 6.26
Nail N. side 9" J. Pine East 36.90
Nail E. side 18" Norway S11°W 71.44

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00

STATE OF MICHIGAN
MARVIN E. MYERS
PROFESSIONAL SURVEYOR
No. 31600
LICENSED PROFESSIONAL SURVEYOR

Signed by _____ Date July 10, 2000

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995