

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda

(County)

Located In:

Corner Code #

Liber 5 Pg. 85

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:27:09 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey

T 27N R 2E

C-1

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Closing corner common to Sections 5 and 6, T27N, R2E

G.L.O. - 1839 William R. Coon D.S.

1969 LCRC L2, P166 K. J. Ostling #10068

Mon - Post

Mon - This corner was established according to the US record 9.9 East of corner to Sec 31-32, T28N, R2E

Wit: 8" Spr. Pine S46°E 54 lks

Wit: 8" Jackpine S34°E 36.7

10" Spr. Pine S71°W 82 lks

8" Jackpine S57°W 24.4

Intersected 0.05 East of C-13

T28N, R2E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Closing corner common to Sections 5 and 6, T27N, R2E

Found DNR Monument; found 8" Jackpine S57°W 24.4. Accepted DNR Monument as a careful and faithful reestablishment of the position of the Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Closing corner common to Sections 5 and 6, T27N, R2E

Mon - Standard DNR Monument.

Wit: Nail E. side 6" J. Pine N08°E 21.78

Nail E. side 8" J. Pine N20°W 23.10

Nail N. side 10" J. Pine S63°W 24.93

16" Norway S70°W 37.47

C-13 is West 9.78

APPROVED

County Monumentation
Peer Review Group

NCC

27 JULY 00



Signed by

Marvin E. Myers

Date July 10, 2000

Surveyor's Michigan License No. 31600