

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located In:

Corner Code #

| | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>27N</u> R <u>2E</u> | <u>C-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Liber 5199 87

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:29:10 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Corner common to Sections 5, 6, 7, and 8, T27N, R2E

G.L.O - 1839 William R. Coon D.S.

L1, P273 Ostling 1982

L195, P6825 Mitchell 10-5-95

Mon - Post

Mon - D.N.R. Monument

Mon - FND D.N.R. Monument

Wit: 8" Spr. Pine N43°E 22 lks

Wit: 9" Jackpine N55°W 52.8'

Wit: FND Blazed 13" Jackpine N52°W 52.9'

6" Spr. Pine S44°W 10 lks

12" Jackpine S63°W 47.5'

FND Blazed 15" Jackpine S63°W 47.32

Set SPK W SD 18" Poplar N10E 43.28

Set SPK W SD 8" Poplar N17°W 37.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner common to Sections 5, 6, 7, and 8, T27N, R2E

Found Standard DNR Pipe & cap; found blazed 13" Jack pine N52°W 52.9(53.03 to nail); found blazed 15" Jackpine S63°W 47.32 (47.69 to nail); found spike W. side 18" Poplar N10°E 43.28; found spike W. side 8" Poplar N17°W 37.6. Accepted Standard DNR Pipe & Cap as the best available evidence of the Position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner common to Sections 5, 6, 7, and 8, T27N, R2E

Mon - Standard DNR Pipe & Cap

Wit: Nail N. side 13" J. Pine N52°W 53.03

Nail S. side 15" J. Pine S63°W 47.69

Nail W. side 18" Poplar N10°E 43.28

Spike W. side 8" Poplar N17°W 37.6

APPROVED
County Monumentation
Peer Review Group
NCC
27 JULY 00



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date July 11, 2000