

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E C-4
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent Restoration.

1/4 corner common to Sections 7, and 8, T27N, R2E
 GLO 1839 W. R. Coon D.S. July 1886 Randall, CS
 Mon. - Post Mon - Set Post 40 chains North
 Wit: 6" Spr. Pine S75°E 46 lks of (C-5) set meander post at 53.7 Chains
 4" Dwarf Oak N75°W 94 lks North of (C-5) at lake in water, but suppose
 to be about 40 lks South of margin of lake.
 Wit: ??? N74 1/2°W 21 1/2 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/4 corner common to Sections 7, and 8, T27N, R2E
 No evidence of GLO or J. Randall post or accessories was found. GLO recorded tie to Muskrat Lake appears to have recorded in error, this was also stated in the field notes of J. Randall. J. Randall County Surveyor ran a line North from C-5 set a Post at 40 chains, and continued North and set a Post in the Lake, but did not go to C-3 as field notes end at the Lake. GLO records the distance C-5 to C-3 as 80 chains. Our measurement was 5270.10. C-4 was set by single proportion measure on line C-5 to C-3 at 2635.05. This position was accepted as a careful and faithful reestablishment of the position of the Corner. Set 5/8"x34" steel rebar with Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to Sections 7, and 8, T27N, R2E
 Mon - Standard County Monument
 Wit: Nail in E. side 14" Norway S15°E 3.98
 Nail SW side 14" J. Pine N70°W 13.05
 Nail NE side 14" Oak N16°E 23.32
 Nail SW side 14" J. Pine S85°E 35.68

APPROVED
 County Remonumentation
 Peer Review Group
 NCC
 27 JULY 00



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date July 11, 2000

Liber 5 pgs. 88-89

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:30:37 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

DEC 21 2000

SECTION

