

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

C-6

Liber 5 pg. 91

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:32:14 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Marvin E. Myers, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 6.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

1/4 corner common to sections 17 and 18, T27N, R2E

G.L.O. William R. Coon, D.S. 1839
Mon: post
Wit: 8" Spruce Pine S62°W 49 links
4" Spruce Pine N42°E 18 links

John R. Randall, County Surveyor, 1885
Mon: Remarkd corner, found U.S. BT's still standing
Wit: 3" Dwarf Oak S36°W 1.13 1/2
4" Dwarf Oak N46°E 1.86

Norman C. Caldwell, P.S. #12018
Certified Survey's, 1967
Mon: Set 1/2" bar by single proportion
Wit: 12" Jack Pine S55°W 34.3'
5" Norway Pine N20°W 47.1'
1/2" bar North 66.0'
14" Jack Pine N65°W 60.7'
4" Norway Pine S60°E 51.5'

1968 Consumers Power Co.
H.W. Dorcay
Mon - Found 1/2" Iron Pin
Wit: Blaze 8" J. Pine SW 33.93
Blaze 12" J. Pine NW 60.55
Blaze 6" Norway NNW 47.22

Norman C. Caldwell, P.S. #12018
L.C.R.C Liber 1 Page 115, 1973
Mon: Found 1/2" bar, Replaced with Standard County Corner.
Wit: 12" Jack Pine S55°W 34.3'
14" Jack Pine N65°W 60.7'
5" Norway Pine N20°W 47.1'
4" Norway Pine S60°E 51.5'
1/2" bar North 66.0'
Placed D.N.R. post alongside

Larry G. Beauregard, P.S.#18654
Survey Liber 193, Page 5866, dated 1993
Mon: Existing Oscoda County Monument
Wit: 15" Jack Pine S55°W 34.3'
8" Norway Pine N20°W 47.1'

17" Jack Pine N65°W 60.7'
7" Norway Pine S60°E 51.5'

Frederick J. King, P.S. # 25852
Survey Liber 199, Page 11404, dated 1999
Mon: Found Record County pipe & Cap
Wit: Bk 1, Pg 115

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/4 corner common to sections 17 and 18, T27N, R2E

Found Standard Oscoda County Corner in centerline of E-W road and West edge of road South; found 7" Norway S60°E 51.5; found 8" (now 18") Norway N20°W 47.1 to blazed face; Accepted Standard Oscoda County Corner as the best available evidence of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to sections 17 and 18, T27N, R2E

Mon - Standard Oscoda County Corner Monument.

Wit: Set nail & tag in S. side 20" Norway S60°E 51.75
Set nail & tag in W. side 8" J. Pine S21°E 50.25
Set nail & tag in N. side 6" J. Pine N45°W 4.68

Signed by Marvin E. Myers

Date July 10, 2000

Surveyor's Michigan License No. 31600

Set nail & tag in E. side 18" Norway N20°W (47.1 to blazed face) 47.41

