

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg 62

For corners in

OSCODA Located In: ELMER Corner Code #
1. Public Land Survey T 27NR 2E C-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN OSCODA COUNTY FILED 15 SEP 1999 9:43:30 AM PATSY J. PETERS REGISTER OF DEEDS Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, FREDERICK J. KING, in a field survey on JUNE 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column B and row 11.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-11 - CORNER COMMON TO SECTIONS 29, 30, 31 & 32
Nov. 1839 - William R. Coon - Dep. Sur. - Set Original Post - N70W-13 1/2 lks(8.91') 15" J. Pine * N10W-8 lks(5.28') 8" Aspen
Oct. 1943 - Sur by G.D. Henning, PS#2240 - Set 1" Pipe by Prop Meas-S41W-58.1'-18" Oak * S53E-81.6'-12" N. Pine*
Sept. 1973 - Act 132 by N.C. Caldwell, PS#12018 - End Rec Henging Pipe - Placed Std CO. Cor-N24 W-56.5'-16" N. Pine
DNR Post alongside * Pwr Line In line EAST * N20 W-56.15'-24" N. Pine * S45 W-58.0'-24" Oak (R) *
S50E-81.3'-16" N. Pine * N10E-28.25'-8" N. Pine (Rec. L.1, Pg. 383)
Sept. 1973 - Act 74 by N.C. Caldwell, PS#12018- Same Info as Act 132 - L.1, Pg. 383 (Rec. Bk 1, Pg. 227)
Aug. 1979 - Act 132 by N.C. Caldwell, PS#12018 - Same Info as Act 132-L.1, Pg. 383 (Rec. L.3, Pg. 106-107)
Jan. 1981 - Act 132 by F.J. King, PS#25852 - End Std CO Cor. - Same Wit as Act 132 Rec. L.1, Pg. 383 (Not Recorded)

B. Description of corner evidence found and/or method applied in restoring or Reestablishing corner:

C-11 - CORNER COMMON TO SECTIONS 29, 30, 31 & 32
End Std Co. Cor & All Rec. Witnesses - (L.1, Pg. 383)

APPROVED
County Remonumentation
Peer Review Group
7 SEPT 99
NCC

THIS CORNER APPROVED BY OSCODA COUNTY PEER REVIEW ON JULY 9, 1999, AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 - CORNER COMMON TO SECTIONS 29, 30, 31 & 32
Staggard County Corner
N10E - 28.42' (R-28.25') - Set S&T on W side of 15" R. Pine
N40E - 0.75' - SW face of USFS Post
S53E -(R-S50E) - 81.98' (R81.3' & 81.6') - Set S&T NE side of 21" R. Pine
S41W -(R-S45 W) - 58.49' (R-58.0' & 58.1') Set S&T SE side 30" Oak
N24 W - (R-N20 W) - 56.35' (R-56.15' & 56.5') Set S&T NE side of 30" R. Pine.
Corner Is In Line with Power Line to East



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date August 28, 1999