

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E D-3
- T R _____
- T R _____
- T R _____
- 2. Property Controlling S T R _____
- in Section S T R _____
- 3. Miscellaneous S T R _____
- Property in Sec. S T R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

¼ corner common to Sections 5 and 8, T27N, R2E
 G.L.O. Marcus Schaaf (Circa 1930's)
 William R. Coon D.S. 1839 Marcus Schaaf Index provided by D.N.R.
 Mon: Post Mon: Found or established and replaced
 Wit: 4" Dwarf Oak N15°E 42 lks Wit: none found
 4" Dwarf Oak S70°W 11lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

¼ corner common to Sections 5 and 8, T27N, R2E
 No evidence of GLO, accessories or subsequence restoration was found. Set 5/8"x34" Steel rebar with Standard Oscoda County Remonumentation Cap by single proportion measurement between C-3 and E-3. Accepted as a careful and faithful reestablishment of the Position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

¼ corner common to Sections 5 and 8, T27N, R2E
 Mon - Standard Oscoda County Monument.
 Wit: Nail in N. side 6" J. Pine S84°E 18.93
 Nail in N. side 6" J. Pine S30°E 35.35
 Nail in S. side 12" Norway S26°W 62.24
 Nail in W. side 12" Norway N28°W 29.75

APPROVED
 County Remonumentation
 Peer Review Group
 NCC
 27 JULY 00



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date July 11, 2000

Liber 5 pgs. 93-94

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:34:04 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3				●									
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

DEC 21 2000

SECTION

