

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E D-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on June 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

1/4 corner common to Sections 8 and 17, T27N, R2E

G.L.O. William R. Coon D.S. 1839 Mon: Post Wit: 4" Spruce Pine N29°W 79 links 4" Spruce Pine N82°E 164 1/2 links
Marcus Schaff (Circa 1930's) Marcus Schaff Index provided by D.N.R. Wit: none found
Norman C. Caldwell, P.S. #12018 Certified Surveys dated 1967 Mon: Found old post and 2" Pipe Wit: 14" Jack Pine S34°E 74.5' 18" Oak S57°W 25.0' 7" Jack Pine N60°E 48.0' 8" Jack Pine N55°W 49.7'

1968 Consumers Power Company H. W. Dorcey Mon - Found 1/2" Iron Rod Wit: Blaze 16" Oak SW 22.04 Blaze 8" J. Pine NW 43.53 Blaze 6" J. Pine NE 48.51
Frederick J. King, P.S. #25852 Survey Liber 198, Page 3648, dated 1998 Survey Liber 199, Page 11404, dated 1998 Mon: Found 1/2" iron, no cap Wit: none provided
Frederick J. King, P.S. #25852 Mon: Found record 1/2" iron Wit: none provided

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/4 corner common to Sections 8 and 17, T27N, R2E

Found 1/2" bar; found 18" (now 22" B. Oak S57°W 25.00 to blaze. Accepted 1/2" bar as the best available evidence of the position of the Original Government Corner. Replaced 1/2" bar with 5/8"x34" steel bar with Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to Sections 8 and 17, T27N, R2E

Mon - Standard Oscoda County Monument. Wit: Nail N. side 10" J. Pine N70°E 53.15 Nail W. side 7" J. Pine S09°E 103.00 Set nail in N. side 22" B. Oak S57°W 25.31 Nail 3' above grade in NE side 8" J. Pine N30°W 52.83

APPROVED County Remonumentation Peer Review Group NCC 27 JULY 00



Signed by [Signature] Surveyor's Michigan License No. 31600

Date July 10, 2000

Register of Deeds Stamp & File Number

Liber 5 Pg. 95

STATE OF MICHIGAN OSCODA COUNTY FILED

9 AUG 2000 3:36:06 PM

PATSY J. PETERS REGISTER OF DEEDS

Grid table with columns A-M and rows 1-13. A dot is marked at row 5, column D.