

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA (County)	Located In: ELMER	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>2E</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 5 pg 66

STATE OF MICHIGAN
OSCODA COUNTY
FILED

15 SEP 1999 9:47:12 AM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, FREDERICK J. KING, in a field survey on June 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- D-11 - 1/4 CORNER COMMON TO SECTIONS 29 & 32
- Nov. 1839 - William R. Coon, Dep. Sur. - Set Original Post - N12°W-71 lks (46.86') 6" Spruce * S48°W-1.3 ch(87.12')6"Spr
- Aug. 1979 - Act 132 by N.C. Caldwell, PS#12018 - Shows Cor Used - No Witness (Rec L.3, Pg. 105)
- Aug. 1979 - Act 132 by N.C. Caldwell, PS#12018 - Set Std CO Cor by Sngl Prop. N45°E-1.0'-DNR Post * N25°E-14.55'-6" R. O S35°W-8.2'-9" R. Oak * N40°W-12.3'-3" R. Maple (Rec. L.3, Pgs 106-107)
- Sept. 1979 - Act 74 by N.C. Caldwell, PS#12018 - Same Info as L.3, Pgs 106-107 (Rec. Bk1, Pg. 227)
- April 1980 - Act 132 by N.C. Caldwell, PS#12018 - Shows Cor Used - No Desc. - No Wit. (Rec. L.3, Pg. 217)
- Jan. 1981 - Act 132 by F.J. King, PS#25852 - Shows Fnd CO Mkr - No Wit (Not Recorded)
- June 1985 - Act 132 by F.J. King, PS#25852 - Shows Fnd CO Mkr - Refers to Bk 1, Pg. 227 (Rec. L.4, Pg. 26)
- Oct. 1992 - Act 132 by L.G. Beauregard, PS#18654 - Fnd CO Cor. (Same Wit as L.3, Pg. 106 (Recorded L. 192, Pg. 6099)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 - 1/4 CORNER COMMON TO SECTIONS 29 & 32
Fnd Std CO Corner & All Rec. Witnesses

APPROVED
County Remonumentation
Peer Review Group

7 SEPT 99
NCC

THIS CORNER APPROVED BY OSCODA COUNTY PEER REVIEW ON JULY 9, 1999, AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-11 - 1/4 CORNER COMMON TO SECTIONS 29 & 32
- Standard Oscoda County Corner
- N25°E - 14.88' - (R 14.55') - Set S&T on W side of 15" Oak
- N45°E - 1.30' - (R-1.0') - Set S&T on NW side USFS Post
- S35°W - 8.30' - (R-8.2') - Set S&T on SE side of 15" Oak
- WESJ - 0.75' - E Face of Steel Fnc Post @ E end of Chain Link Fence
- N40°W - 12.27' - (R-12.3') - Set S&T on NE side of 6" Maple



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date August 28, 1999