

**SURVEY &
REMONUMENTATION**

MAR 19 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Liber 4 pg 148

For corners in Oscoda <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 27N R 2E	D - 13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

26 NOV 96 3:03 P.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on June 27, 1996
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - L. Clason 1838 Mon.-Post WIT: 8" Y.Pine N73°W 28 lks. 9" W.Birch N61½°E 17 lks. 2' wide brook East 2.8 chs. 1.32' wide brook West 6.05 chs.	GLO 1935 Guy Veal Mon.-Brass Tablet in conc. mon. set from stump of original B.T. WIT: brook 3 lks. wide East 3.02 lks. 10" Norway pine stump N73°W 28 lks. 6" Norway N51½°E 12½ lks. 6" Poplar N62½°W 56 lks.
1909 Fargo Eng. Mon.-Not given WIT: Fd. gov't BT 12" Y.Pine N13°E 17' 12" Y.Pine S32°E 43'	

Liber 3, pg. 422
Oct. 1979 Edwin J. McCombs
Mon.-Conc. mon. & cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found brass tablet in 6" concrete
Found 12" yellow pine stump with blaze
And is accepted as a careful and faithful perpetuation of the position of the original corner
Standard South ½ Corner, T27N, R2E

APPROVED
County Remonumentation
Peer Review Group

*NCC
16 NOV 96*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found U.S. GLO concrete monument with Brass Cap, left in place
WIT: 8" Norway nail W. side N15°E 10.48'
Nail S. side 15" Norway N68°W 33.80'
Nail SW died 7" Norway S28°E 7.61'
Nail side 4" W.Pine N36°W 20.77'



Signed by Marvin E. Myers

Date Sept 7, 1996

Surveyor's Michigan License No. 31600