

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg 96

For corners in

Oscoda
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E E-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:37:06 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Closing corner common to Sections 4 and 5, T27N, R2E

G.L.O. - 1839 William R. Coon DS circa 1930 M. Schaaf
 Mon - Set Post Found, established or remarked
 Wit: 30" Y. Pine S30°E 50 lks
 20" Y. Pine S56 1/2°W 52 lks
 Intersected 0.50 East of E-13
 T28N, R2E

L2, P163 Ostling 1969

Found 1 1/2" Pipe in place, previously established by Schaaf. Both closing corner USBT stumps in place, the SW with good face. Set DNR Mon.
 Wit: 12" B. Oak S32°W 32.6'
 12" Red Pine S68°E 105.9'
 U.S.B.T. 14" Y. Pine Stp S58°W 34.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Closing corner common to Sections 4 and 5, T27N, R2E

Found Standard DNR Pipe and Cap. Accepted DNR pipe as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Closing corner common to Sections 4 and 5, T27N, R2E

Mon - Standard DNR Monument.
 Wit: Spike in NW side 20" B. Oak N60°E 24.87
 E-13 is West 27.36
 Nail W. side 8" B. Oak S40°E 38.19
 Nail in West side 12" W. Pine S40°W 41.51
 Nail E. side 4" W. Pine N45°E 14.33

APPROVED
 County Remonumentation
 Peer Review Group
 NCC
 27 JULY 00



Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

Date July 10, 2000