

DEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber 5 pgs. 99-100

Oscoda
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 2E E-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:40:40 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on June 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3					●								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Corner common to Sections 4, 5, 8 and 9, T27N, R2E
G.L.O - 1839 William R. Coon, DS 1887 John Randall, CS
Mon - Post Mon - 18" Y. Pine S50°E 147 lks
Wit: 6" Aspen S63°W 17 lks No other
6" Spr. Pine S74°E 8 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner common to Sections 4, 5, 8 and 9, T27N, R2E
No evidence of GLO or subsequent restoration, reestablished corner position by double proportion measure from E-1 to E-5 and C-3 to G-3. This position was accepted as a careful and faithful reestablishment of the position of the Government Corner. Set 5/8"x34" Steel Rebar with Standard Oscoda County Remonumentation Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner common to Sections 4, 5, 8 and 9, T27N, R2E
Mon - Standard Oscoda County Monument.
Wit: Set Nail & tag E. side 10" Norway N30°E 6.44
Set nail & tag S. side 14" Norway S80°E 8.65
Set nail & tag S. side 10" Spruce Pine N80°W 3.21
Set nail & tag E. side 8" Norway N24°W 13.32

APPROVED
County Remonumentation
Peer Review Group
NCC
27 JULY 00



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date July 11, 2000

DEC 21 2000

SECTION

