

JEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda

(County)

Located In:

Corner Code #

Liber 5 Pg - 104

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

9 AUG 2000 3:43:22 PM

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey

T 27N R 2E

E-6

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on June 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

1/4 corner common to Sections 16 and 17, T27N, R2E

G.L.O. - 1839 William R. Coon

1887 John Randall C.O.

L2,P173 N.C. Caldwell 1969

L3,P321 L.G. Beauregard 81-91-95

Mon - Post

Mon - Post Sec 17 & 16

Mon - Cap & Pipe

Mon - Standard Co. Corner

Wit: 10" Y. Pine N80°W2.32

Wit: 4" Spr. Pine S45 1/2°E 151/2

Wit: 12" Jackpine N45°E 3.0

Wit: 12" Jackpine N45°E 3.0

12" Y. Pine S73°W 1.47

No other

8" Jackpine S35°E 17.4

8" Jackpine S35°E 17.4

12" Jackpine S65°W 18.4

12" Jackpine S65°W 18.4

1968 Consumers Power Company H.W. Dorcey

Mon - Not given

Wit: None given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/4 corner common to Sections 16 and 17, T27N, R2E

Found Standard Oscoda County Corner; found 12" J. Pine stump N45°E 3.0; found 8" J. Pine stump S35°E 17.4; found 12" J. Pine stump S65°W 18.4. Accepted Standard County monument as the best available evidence of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to Sections 16 and 17, T27N, R2E

Mon - Standard Oscoda County Monument

Wit: Nail & tag S. side 4" J. Pine N70°E 7.85

Nail & tag N. side Dept of Conservation Post N45°E 0.70

Nail & tag N. side 3" J. Pine S55°E 33.00

Nail & tag E. side 4" W. Pine S20°W 27.55

APPROVED  
County Remonumentation  
Peer Review Group  
NCC  
27 JULY 00



Signed by

*Marvin E. Myers*

Date July 10, 2000

Surveyor's Michigan License No. 31600