

JEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)

Located In:

Corner Code #

1. Public Land Survey

T 27N R 2E

F-1

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Liber 5 pg. 105

STATE OF MICHIGAN
OSCODA COUNTY
FILED

9 AUG 2000 3:44:07 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on June 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Cell F4 contains a circled '4'.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

Closing N 1/4 corner Section 4, T27N, R2E
Not set by GLO

1916 Clarence O. Seeley CS
Mon - Post
Wit: 8" Aspen NW 1.94
Post 45 Links West of Creek

1969 DNR K. Ostling #10068
Mon - 1"x36" Iron Pipe
Wit: 7" W. Pine S64°W 35.2
3" W. Pine S62°E 19.9

Nov 1993 D. Porter #15410
Mon - Fd. 1" pipe cons Dept cap missing place Porter cap in Pipe #15410
Wit: 14" J. Pine S14°W 24.24
12" W. Pine S68°W 35.13
8" J. Pine N61°W 46.89
8" W. Pine N15°W 42.45

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Closing N 1/4 corner Section 4, T27N, R2E

Found 1" pipe with Cap #15410 inside; found nail & tag SE side 14" W. Pine S68°W 35.13; found nail N. side & tag N. side 8" J. Pine N61°W 46.89.1 Accepted pipe as a careful and faithful establishment of the Corner. Drove 5/8" bar inside pipe and placed standard Oscoda County Remonumentation Cap on bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Closing N 1/4 corner Section 4, T27N, R2E
Mon - Standard Oscoda County monument.

Wit: Nail & tag SE side 14" W. Pine S68°W 35.13
Nail N. side & tag N. side 8" J. Pine N61°W 46.89
Nail N. side 7" W. Pine S50°E 18.56
F-13 is West 23.75
Nail E. side 24" Norway N30°W 83.83

APPROVED

County Remonumentation
Peer Review Group

NCC
27 JULY 00



Signed by

[Signature of Marvin E. Myers]

Date July 10, 2000

Surveyor's Michigan License No. 31600