

JEC 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda  
(County)

Located in:

Corner Code #

- 1. Public Land Survey      T 27N R 2E      F-3
- T     R
- T     R
- T     R
- 2. Property Controlling    S     T     R
- in Section               S     T     R
- 3. Miscellaneous           S     T     R
- Property in Sec.        S     T     R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on June 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration.**

¼ corner common to Section 4 and 9, T27N, R2E

GLO W. R. Coon, DS  
Mon. - Post  
Wit: 8" Y.Pine S59°W 7 lks  
6" W.Pine N63°W 9 lks

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

¼ corner common to Section 4 and 9, T27N, R2E

No evidence of GLO or subsequent restoration was found, reestablished position by single proportion measure. Accepted position as a careful and faithful reestablishment of the Government Corner. Set 5/8"x34" steel rebar with Standard Oscoda County Remonumentation cap.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

¼ corner common to Section 4 and 9, T27N, R2E

Mon - Standard Oscoda County Monument  
Wit: Nail & tag S. side 8" Oak S88°E 4.68  
Nail & tag W. side 14" Oak S02°E 9.24  
Nail & tag N side 12" Oak N66°W 18.51  
Nail & tag E. side 3" Maple N15°W 12.40

APPROVED  
County Remonumentation  
Peer Review Group  
NCC  
27 JULY 00

Liber 5 pgs. 106-107

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

9 AUG 2000 3:45:01 PM

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3						●							
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date July 11, 2000



JEC 21 2000

SECTION

