

SURVEY & REMONUMENTATION

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 pg 150

For corners in Oscoda (County) Located in: Corner Code #

1. Public Land Survey	T	<u>27N</u>	R	<u>2E</u>	<u>F - 13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED
 26 NOV 96 3:05 P.M.
 PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 27, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1838 L. Clason Mon.-Post WIT: 6" Aspen N73°W 16 lks. 6" W.Pine N32½°E 13 lks.	GLO - 1935 Guy Veal Mon.-Set brass tablet in 6" conc. proportionately WIT: 10" Norway N32 3/4°E 81½ lks. 8" Poplar N51°W 98 lks. .125 lks. to closing cor.	Liber 194, page 3382 May 1994 Larry Beauregard Mon.-½" bar in pav't box
--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" bar in pavement box
 And is accepted as a careful and faithful reestablishment of the position of the original corner
 Standard Corner T27N, R2E

APPROVED
 County Remonumentation
 Peer Review Group

*NCC
 16 NOV 96*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced record ½" Bar with Standard Oscoda County Monument in pav't box
 WIT: PK in top guard rail post N52°E 26.81'
 PK in top guard rail post N51°W 37.05'
 PK in top guard rail post S75°W 42.23'
 PK in top guard rail post S30°E 19.94'
 Distance between cor. 8.19'



Signed by Marvin E. Myers Date September 7, 1996

Surveyor's Michigan License No. 31600