

**SURVEY &  
REMONUMENTATION**

08T 17 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 2E</u>	<u>G-8</u>
	Sec. T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
4. Lot No. <u>          </u> , Recorded Plat <u>          </u>		
5. Private Claims <u>          </u>		

**SECTION**

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

3 SEP 1999 1:43:13 PM

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File  
Number

*Liber 5 Page 23*

I, Marvin E. Myers, in a field survey on June 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-8 = 1/4 Cor. Sec 21 & 22, T27N, R2E

GLO Nov 1839 William R. Coon, DS  
Mon - Post

Wit: 8" Birch S25°W 49 lks  
10" Fir N62°E 14 lks

Co. Surveyor Bk 2, P. 86 Dec 11<sup>th</sup> 1914

C. O. Seeley, County Surveyor

Mon - Fd. Randall's Post & BT's

Set 2"x18" Iron Pipe at stake

Wit: NBT 12" Beech N32 1/4°W 0.50  
NBT 9" Sugar S35°W 0.46

Co. Surveyor Book 1, Page 215

Oct 1<sup>st</sup> 1887 J. Randall Co. Surveyor

Mon - Set Post

Wit: 10" Sugar N11 1/2°W 27 lks  
12" Beech S40°E 47 lks

Cons. Power Co. H. Dorcey #9429 Nov 1967

Mon - Not given

Wit: None given

June 6<sup>th</sup> 1968 N. Caldwell, #12018

Mon - fd. 2" Pipe by Seeley

Wit: 8" Maple S15°W 16.6'

6" Maple S65°W 21.8'

14" Maple N15°W 13.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 = 1/4 Cor. Sec 21 & 22, T27N, R2E

Mon - Found 2" pipe in N-S tree line in nest of stones in line with brush line West.

Wit: Found 13" Maple S15°W 16.6

Found 16" Maple N15°W 13.4

Accepted pipe as a careful and faithful establishment of the position of the Government Corner, placed 5/8" rebar with Standard Oscoda County Cap inside existing 2" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 = 1/4 Cor. Sec 21 & 22, T27N, R2E

Mon - 5/8" rebar with Standard Oscoda County Cap inside existing 2" pipe.

Wit: Spike E. side 13" Maple S15°W 16.75

Spike S. side 6" Maple S75°W 22.12

Spike W. side 16" Maple N15°W 13.99

Spike N. side 4" Cherry N87°E 13.55

**APPROVED**

County Remonumentation  
Peer Review Group

*19 AUG 99  
NCC*



Signed by *Marvin E. Myers*

Date Aug 14, 1999

Surveyor's Michigan License No. 31600