

**SURVEY &
REMONUMENTATION**

OCT 17 1999

STATE OF MICHIGAN
OSCODA COUNTY
FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

3 SEP 1999 1:47:09 PM

PATSY J. PETERS
REGISTER OF DEEDS

<u>Oscoda</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 2E</u>	<u>G-12</u>
	Sec. T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims <u> </u>		

Register of Deeds Stamp & File
Number

Libel 5 Page 27

I, Marvin E. Myers, in a field survey on June 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12 = 1/4 Cor. Sec 33 & 34, T27N, R2E

GLO Nov 1839 William R. Coon, DS

Mon - Post

Wit: 9" Hemlock N14°W 3 lks

10" Hemlock N31°E 6 lks

Co. Surveyor Bk 2, P. 33 June 18th 1913

C. O. Seeley, County Surveyor

Mon - Set Post

Wit: Marked 5" R. Oak N41°E .61 1/2

Co. Surveyor Book 1, Page 215

Oct 1st 1887 J. Randall Co. Surveyor

Mon - Set Post

Wit: NBT 6" Cedar N35°E 25 1/2

NBT 7" Cedar N80°W 23

Co. Surveyor Bk 2, P. 118 Nov 4th 1915

Mon - Set 1"x14" Gas Pipe

Wit: NBT W. P. Stump S57°E 0.62

Cons. Power Co. H. Dorcey #9429 Nov 1967

Mon - found Nail

Wit: 2± E & 19± S. of Fence Corner

Norman C. Caldwell, R.L.S. #12018

LCRC L. 1, P. 40 July 1971

Mon - fd. Seeley 1"x14" Gas Pipe

Wit: 14" W. Pine Stump S57°E 40.9

Fence Cor. 14' N & 4' E

5" Cedar S45°W 6.3'

4" Cedar N10°E 4.0'

10" Cedar S60°E 32.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 = 1/4 Cor. Sec 33 & 34, T27N, R2E

Mon - Found 1" Pipe & found "T" Iron S42°W 3.85

Wit: 5" Cedar Stump S45°W 6.3

4" Cedar Stump N10°E 4.0

Pipe is in new E-W fence row that is 4± West of N-S fence row, also an older E-W fence is North 14±. Accepted Pipe as a careful and faithful establishment of the position of the Corner. Placed 5/8" Rebar with Standard Oscoda County Cap inside pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 = 1/4 Cor. Sec 33 & 34, T27N, R2E

Mon - 5/8" Rebar with Standard Oscoda County Cap inside existing pipe.

Wit: "T" Iron S42°W 3.85

Nail SE side 5" Cedar S62°W 7.00

Nail SW side 5" Cedar S42°W 13.45

Nail E. side 8" Cedar S10°W 14.70

Nail S. side 4" Cedar S74°E 7.68

APPROVED

County Remonumentation
Peer Review Group

*12 AUG 99
NCC*



Signed by *Marvin E. Myers*

Date Aug 14, 1999

Surveyor's Michigan License No. 31600