

**SURVEY &
REMONUMENTATION**

NOT TO SCALE

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

STATE OF MICHIGAN
OSCODA COUNTY
FILED

3 SEP 1999 1:50:02 PM

PATSY J. PETERS
REGISTER OF DEEDS

Liber 5 Page 30

Register of Deeds Stamp & File
Number

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 2E</u>	<u>H-11</u>
	Sec. T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Marvin E. Myers, in a field survey on June 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11 = 1/4 Corner common to Sections 27 & 34, T27N, R2E

GLO Nov 1839 William R. Coon, DS
Mon - Post
Wit: 10" Aspen S13°W 62 lks
8" Aspen N13°E 28 lks

LCRC L. 1, P. 207
June 1st 1978 N. Caldwell #12018
Mon - Fd. Rec. Iron in pav't replaced
with Standard County Corner.
Wit: 6" Apple S55°W 69.0'
1/2" bar & cap North 33.00'
Centerline of road South is E. 12±
L2, P 601 same as above

June 1964 N. Caldwell #12018
Mon - Not given
Wit: Pipe SW on RW

Nov 1967 Consumers Power
H. Dorsey #9429
Mon - Fd. nail
Wit: none given

L3, P 326 Nov 9, 1981 R. Higgins #21570
Mon - Fd. Oscoda Co. Mon
Wit: Fence Post N28°W 39.59'
Cor. Fence Post N10°E 34.32'
Power Pole N50°E 63.55'
Cor. Fence Post S50°E 58.15'
LCRC L1, P 275 same as above

L 1, Pg 24 N. Caldwell #12018
July 29, 1971
Mon - Not given
Wit: None given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 = 1/4 Corner common to Sections 27 & 34, T27N, R2E
Mon - Found Standard County Corner in intersection of Kittle & Camp Ten Road 0.3 below surface

Wit: Found Power Pole N50°E 63.55'
Found Cor. Fence Post S50°E 58.15'
Found nail & tag in NW side Box Alder S35°W 60.60'
Found nail & tag in SW side 2" twin Apple N20°W 49.30'

Accepted Standard County Corner as the best available evidence of the position of the Original Government Corner placed in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 = 1/4 Corner common to Sections 27 & 34, T27N, R2E
Mon - Standard County Corner Monument in pavement monument box.

Wit: Power Pole N50°E 63.55'
Cor. Fence Post S50°E 58.15'
Nail & tag in NW side Box Alder S35°W 60.60'
Nail & tag in SW side 2" twin Apple N20°W 49.30'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P. Pole N45°E 63.6'
Sept 25th 1990 F. King #25852
Mon - Fd. Rec. Cor.
Wit: Bk. 1, Pg. 206

APPROVED

County Remonumentation
Peer Review Group

19 AUG 99
NCC



Signed by *Marvin E. Myers*

Date August 14, 1999

Surveyor's Michigan License No. 31600