

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

001 17 888

For corners in

SECTION

3 SEP 1999 1:53:04 PM

Oscoda
(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|-------------------------|-------|-------|
| 1. Public Land Survey | Sec. T 27NR 2E | _____ | 1-9 |
| | Sec. T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Liber 5 Page 33

I, Marvin E. Myers, in a field survey on May 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-9 = Corner Common to Sections 22, 23, 26 & 27, T27N, R2E
 GLO Nov 1839 William R. Coon, DS July 7th 1955 G. Henning #2240
 Mon - Post Located from witness of record
 Wit: 10" Fir N42½°W 15 ½ lks by Seeley and remarked by me 1934
 10" birch S12°E 7 lks Set iron bar 1 ¼"x14" in center Road.
 Wit: Stone 24" dia. Flat S27½°E 60.4'
- Co. Surveyor Book 2, Page 24
 April 27th 1912 C. Seeley, Co. Surveyor July 30th 1966 N. Caldwell #12018
 Mon - US cor. remarked Mon - Set ¾" Pipe by reconstruction of
 Wit: None given G. Henning survey of record.
 Wit: No references available
- Bk. 3, Pg 148 May 18th 1934
 G. Henning #2240 Nov 1967 Cons. Power Co. by
 Mon - located from Seeley's wit H. Dorsey #9429
 Set 1 ½"x14" iron at cor. Mon - Fd. Iron Pipe
 Wit: Center of N-S Road Wit: Tag In P. Pole NE 57.6'
 Stone 24" dia flat S27½°E 60.4' Tag In P. Pole SE 71.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	10			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

Norman C. Caldwell, R.L.S. #12018
 June 1, 1978 Liber 2, Page 601
 Mon - Fd. Rec. Iron In pavement,
 replaced wit Std. Co. Cor. this date.
 Wit: Tag In P. Pole NE 57.6'
 Tag In P. Pole SE 71.0'
 Centerline road E. 3.3
 LCRC L1, P. 207 N. Caldwell #12018
 Same as above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-9 = Corner Common to Sections 22, 23, 26 & 27, T27N, R2E
 Mon - Found Standard Oscoda County Monument
 Wit: Found nail & tag in P. Pole N48°E 57.65
 Accepted Standard Oscoda County Monument as a perpetuation of the Original Government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-9 = Corner Common to Sections 22, 23, 26 & 27, T27N, R2E
 Mon - Standard County Monument in pavement monument box.
 Wit: Nail & tag in P. Pole N48°E 57.65
 Nail & tag NE side of Fence Post S41°E 48.03
 Nail & tag 6" Elm S60°W 49.56
 GTE marker post N51°W 48.73
 Nail & tag #18654 S. side of Corner Fence Post N64°E 63.66

APPROVED

County Remonumentation
Peer Review Group

19 AUG 99 NCC



Signed by Marvin E. Myers

Date August 14, 1999

Surveyor's Michigan License No. 31600