

**SURVEY &
REMONUMENTATION**

OCT 17 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

For corners in

<u>Oscoda</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 2E</u>	<u>I-11</u>
	Sec. T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

3 SEP 1999 1:55:04 PM

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Liber 5 Page 35

I, Marvin E. Myers, in a field survey on May 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11 = Corner common to Sections 26,27, 34, & 35, T27N, R2E
GLO Nov 1839 William R. Coon, DS Consumers power survey by Dorcey
Mon - Post Nov 1967
Wit: 6" Aspen N57°W 34 lks Mon - fd. 3/4" Pipe
8" Birch N14°E 7 1/2 lks Wit: Nail in E. side T. Pole SE 46.45'
Nail in S. side T. Pole NW 44.78'
Nail in W. side P. Pole NE 47.83'

May 15th 1885 J. Randall Co. Surveyor
Bk 2, Page 17
Mon - not given
Wit: 7" Cedar N77°W 23 1/2
12" Cedar S37°E 40 2/3

L. 2, P. 601 June 1st 1978 N. Caldwell #12018
Mon - Fd. Record iron replaced with
Standard County Corner
Wit: Power Pole N50°E 47.8'
Power Pole S50°W 45.5

Co. Surveyor Book 2, Page 24
April 25th 1912 C. Seeley, Co. Surveyor
Mon - Int 22 links W. of Cor.
Did not describe cor. fd.
Wit: None given

LCRC L1, P207 same as above
Oct 29, 1987 F. King #25852
Mon - Fd. Rec. Std. Co. Cor.
Wit: Rec. Bk 1, P. 207

Co. Surveyor Book 3, Page 160
April 7th 1934 G. Henning #2240
Mon: Cor. Mkd. By Iron Pin
Wit: as per page 17 book 2

L. 4, P. 332
Oct 6th 1988 F. King #25852
Mon - Fd. Rec. Std. Co. Cor.
Wit: Rec. Bk 1, P. 2

1964 N. Caldwell #12018
Mon - fd Boat spike & rock with Pipe
Wit: P. Pole N15°E 47.88'
T. Pole N45°W 44.85'
T. Pole S50°E 46.42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 = Corner common to Sections 26,27, 34, & 35, T27N, R2E
Mon - Found Std. Co. Cor. in centerline intersection Kittle Road E-W and Galbraith Road N-S.
Wit: Found Spike in E. side Power pole N51°E 48.65; found nail & tag in cor. fence post S34°E 50.5; found Spike in E. side Power Pole S46°W 43.82; found nail & tag in NE side Corner Fence Post N40°W 46.99
Accepted Standard County Monument as the best available evidence of the position of the Original Government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 = Corner common to Sections 26,27, 34, & 35, T27N, R2E
Mon - Standard County Monument in pav't monument box.
Wit: Nail & tag in NE side Corner Fence Post N40°W 46.99
Spike in E. side Power Pole S46°W 43.82
Nail & tag in cor. fence post S34°E 50.5
Spike in E. side Power pole N51°E 48.65

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date August 14, 1999

APPROVED

County Remonumentation
Peer Review Group

19 AUG 99

NCC

