

**SURVEY &
REMONUMENTATION**

STATE OF MICHIGAN
OSCODA COUNTY
FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

3 SEP 1999 1:57:05 PM

For corners in

<u>Oscoda</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sec. <u>T 27N R 2E</u>	<u>J-7</u>
	Sec. T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File
Number

Liber 5 Page 37

I, Marvin E. Myers, in a field survey on June 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-7 = 1/4 Corner common to Sections 14 & 23, T27N, R2E
GLO Nov 1839 William R. Coon, DS July 30th, 1966 N. Caldwell #12018
Mon - Post Mon - 1/2" bar by Single Prop.
Wit: 10" Aspen S14°E 6 lks Wit: Iron Pipe South 33.00
6" Aspen N39°W 10 1/2 lks

June 14th 1993

May 18th 1934 G. Henning #2240 L 2, P 593 May 5th 1978 N. Caldwell #12018
Mon - Fd. 4" Iron Casing Mon - Not given
Wit: no witness in evidence Wit: Record Iron found South 33.00'
4" Cedar S...Eft

L. Beauregard #18654
Mon - Ex. Bar In Mon. box
Wit: None given

July 7th 1955 G. Henning #2240 L 4, P 92 May 12th, 1986 L. Beauregard #18654
Mon - Set 3/4"x16" Iron Bolt (1934) Mon - Ex. 1/2" bar in Mon. Box
Wit: 10" Elm E. 38' Wit: 2' S. of centerline of Road

Mar. 25th 1992 Oscoda Co. Rd. Commission
Mon - 1/2" rebar in Mon. box.
Wit: none given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 = 1/4 Corner common to Sections 14 & 23, T27N, R2E
Mon - Found 1/2" rebar in Mon. box.
Accepted 1/2" bar as a careful and faithful establishment of the position of the Corner. Placed Standard County Cap on 1/2" bar in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 = 1/4 Corner common to Sections 14 & 23, T27N, R2E
Mon - 1/2" rebar with Standard County cap in pav't monument box.
Wit: Spike in W. side 10" Cedar N10°E 34.74
Mag nail SW side 14" Cedar N60°E 59.54
Nail SE side 7" Cedar S52°W 48.04
Nail W. side 12" Cedar S10°W 44.04

APPROVED

County Remonumentation
Peer Review Group

12 AUG 99
NCC



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date August 14, 1999