

007 17 12

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
OSCODA COUNTY
FILED

For corners in

3 SEP 1999 1:58:02 PM

PATSY J. PETERS
REGISTER OF DEEDS

<u>Oscoda</u> # _____ (County)	Located In:	Corner Code
1. Public Land Survey	Sec. T <u>27NR 2E</u>	<u>J-9</u>
	Sec. T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Liber 5 Page 38

I, Marvin E. Myers, in a field survey on June 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9 = 1/4 corner common to Sections 23 & 26, T27N, R2E
 G.L.O. Nov 1839 W. R. Coon D.S. July 30th 1966 N. Caldwell, #12018
 Mon: Post Mon - Fd. 2" Pipe & 2 NBT by Henning
 Wit: 8" Cedar N36°W 19 lks Wit: Stone with X North 33.00'
 8" Cedar N60°E 10 1/2 lks Stone with X South 33.00'

5-18-1934 G. Henning, #2240 July 12th 1994 F. J. King, #25852
 Book 3 Page 148 Mon - No corner found set I & C by single
 Mon - 1 1/2" X 16" Pipe in Cor. Prop. from East.
 Wit: 10" Stones with cross in top buried flush with ground at 33 ft. N & S of Cor. Wit: 5'± North of Centerline E-W Road
 2± East of Fence to the North
 E. Gate Post N40°E 36.90
 W. Gate Post S40°W 57.80
 Fence Cor. Post N05°W 33.19

July 7, 1955 G. Henning #2250
 Mon- Est. & Mark 1934 1 1/2" Pipe
 Wit: 10" Stones with cross in top buried flush with ground at 33 ft. N & S of Cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 = 1/4 corner common to Sections 23 & 26, T27N, R2E
 Found 1/2" Bar & Cap with accessories established by Fred J. King July 12th 1994.
 Accepted 1/2" bar as a careful and faithful establishment of the position of the Corner. Placed Standard Oscoda County Cap on 1/2" bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 = 1/4 corner common to Sections 23 & 26, T27N, R2E
 Mon - Standard Oscoda County Monument
 Wit: Nail & tag E. side fence post South 40.26
 Nail & tag W. side Gate Post N33°E 36.88
 Nail & tag W. side corner fence post North 33.22
 Nail & tag West Gate post S51°W 57.90

APPROVED

County Remonumentation
Peer Review Group

*19 AUG 99
NCC*



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date August 14, 1999