

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 17 1999

STATE OF MICHIGAN
OSCODA COUNTY
FILED

For corners in

SECTION

3 SEP 1999 1:59:00 PM

PATSY J. PETERS
REGISTER OF DEEDS

<u>Oscoda</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sec. T <u>27NR 2E</u>	<u>J-11</u>
	Sec. T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File
Number

Liber 5 Page 39

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on June 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11 = 1/4 Corner common to Sections 26 & 35, T27N, R2E

GLO Nov 1839 William R. Coon, DS

Mon - Post

Wit: 8" Cedar S28°E 39 lks

10" Cedar N27°W 54 lks

L. 3, P. 284 July 27th 1981

April 27th 1912 C. Seeley Co. Surveyor N. Caldwell #12018

Mon - Not given

Wit: None given

Mon - Fd. 1/2" bar in pavement

Wit: Fence Post N05°W 44.8'

T. Pole S65°E 54.3

June 30, 1967 N. Caldwell #12018

Mon - 1/2" Bar set

Wit: Cor. Fence Post N05°W 44.8'

T. Pole S65°E 54.3

LCRC L1, P 259 same as above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 = 1/4 Corner common to Sections 26 & 35, T27N, R2E

Mon - Found 1/2" bar in 10' fill section embedded in asphalt.

Wit: Found Fence Post N05°W 44.8'

Accepted 1/2" bar as a careful and faithful establishment of the position of the Corner. Placed Standard Oscoda County Cap on bar in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 = 1/4 Corner common to Sections 26 & 35, T27N, R2E

Mon - 1/2" rebar with Standard County Cap in pavement Monument.

Wit: Spike in side of fence post S65°E 41.88'

Fence Post N05°W 44.8'

Spike E. side 6" Twin Elm N03°E 50.22'

Spike in E. side 6" Thornapple N28°W 41.73'

APPROVED

County Remonumentation

Peer Review Group

12 AUG 99

NCC



Signed by Marvin E. Myers

Date August 14, 1999

Surveyor's Michigan License No. 31600