

JEG 21 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 5 pg. 145

For corners in

OSCODA Located In: ELMER Corner Code #  
(County)

1. Public Land Survey	T 27N R 2E	L-1
	T 28N R 2E	L-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

12 OCT 2000 9:19:03 AM

PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		10		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, FREDERICK J. KING, in a field survey on June 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 - NORTH 1/4 CORNER SECTION 1 (27-2) AND SOUTH 1/4 CORNER SECTION 36 (28-2)

NOT SET ON ORIGINAL GOVERNMENT SURVEY

Dec. 1969 - Sec Division Sur of Sec 36, T28N-R2E by K.J. Ostling, PS#10068 for DNR - Fnd Stake previously established Not Recorded by Schaaf in 1934 - 1 1/2" Pipe - Has been used for Road Easement - Set DNR 1" Pipe & Cap Shows L-1 (27-2) to be common with L-13 (28-2)

July 1970 - LCRC by K.J. Ostling, PS#10068 - Same Infor as above 1969 Sec Division Rec L. 2, Pg. 291 (1) S.24\*W-24.7'-3" R.Pine (2) S.33\*E-60.0'-3" R.Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 - NORTH 1/4 CORNER SECTION 1 (27-2) AND SOUTH 1/4 CORNER SECTION 36 (28-2)

Found Rec DNR Pipe & Cap  
Witnesses Fnd 1 & 2

APPROVED

County Monumentation  
Peer Review Group

29 SEPT 00



THIS CORNER APPROVED BY PEER REVIEW ON JULY 7, 2000, AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

L-1 - NORTH 1/4 CORNER SECTION 1 (27-2) AND SOUTH 1/4 CORNER SECTION 36 (28-2)

Found Rec. DNR Pipe and Cap - Placed Carsonite Marker Post on South sd of Corner. -Corner is +14' South of C.L. of E-W 2-track trail. - Corner is -193' East of C.L. of NW - SE Grav. Rd. (Pennsylvania Crossing Rd.)

N75°E - 14.85' - Set S&T South sd 12" W. Pine  
Wit #2 - S33°E 60.07' (R-60.0') - Set S&T West sd 12" R. Pine - S15°W - 5.59' - Set S&T above Tag 15410 - East sd. 10" R. Pine

Wit #1 - S24°W - 24.68' (R-24.7') - Set S&T West sd 12" R. Pine - N75°W - 27.02' - Set S&T above Tag #15410 - S. Sd 10" R. Pine

Typical Witness Set = 16-D Spk & 1 1/4" Plastic ID Tag (S&T)

Signed by Frederick J. King  
Surveyor's Michigan License No. 25852

Date Sept. 15, 2000