

**SURVEY & REMONUMENTATION**

MAR 19 1997

COMMISSION

*Liber 4 Pg 161*

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 27N R 2E	M - 5 ✓
	T 27N R 3E	A - 5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED

26 NOV 96 3:17 P.M.

PATSY J. PETERS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO Lewis Clason May 1839 Mon.-(A)Set Post WIT: (1)24" Hemlock S40°W 40 lks. (2)12" B.Ash,N37°W 38 lks.	Norm Caldwell May 22, 1970 Mon.-(B)Fd. 1½" pipe (C)Placed Std. Co. Cor. WIT:(4)P.Pole S45°E 72.5' (5)7" Cedar N70°W 72.13' (6)8" Cedar S21°W 87.11' (7)T.Pole S35°W 67.7'	Frederick King June 13, 1988 Liber 4, page 306 Mon.-Fd. (C) Frederick King June 16, 1989 Liber 4, page 389 Mon.-Fd. (C) Carl Johnson June 5, 1985 Mon.-Fd. (C)
E.P. Albertson Dec. 30, 1901 Mon.-None given WIT: Fd. (2) (3)13" Cedar stump S48°40'E 46 lks.	Norm Caldwell Oct. 12, 1970 LCRC Liber 2, page 307 Mon.-(B), (C) (cap & pipe) WIT: (4), (5), (6) & (7)	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Standard Oscoda County Monument in centerline Mount Tom Road 9'± North of Helmer Lake Road West. And is accepted as a careful and faithful perpetuation of the position of the original corner Township corner common to Sections 12 & 13, T27N, R2E and Sections 7 & 18, T27N, R3E

**APPROVED**

County Remonumentation  
 Peer Review Group

*NCC  
 16 NOV 96*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found record-Standard Oscoda County Monument  
 WIT: Nail NE side Power Pole 3.5' above S32°E 66.49'  
 Nail N. side 8" Balsam Gilard S73°E 95.37'  
 Nail E. side 19" Cedar S34°W 86.80'  
 Nail E. side 4' above ground Poplar N20°W 70.85'



Signed by Marvin E. Myers Date Sept 7, 1996  
 Surveyor's Michigan License No. 31600