

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4-Pg 16c

For corners in Oscoda (County)	Located in:	Corner Code #
1. Public Land Survey	T 27N R 2E	M - 12 ✓
	T 27N R 3E	A - 12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 OSCODA COUNTY
 FILED

26 NOV 96 3:24 P.M.

PATSY J. PETERS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Lewis Clason May 1839 Mon.-(A)Set post WIT: (1)8" S.Maple S80°W 15 lks. (2)8" W.Birch N49°W 32 lks.	Norm Caldwell Jan. 30, 1979 LCRC Liber 1, page 224 Mon.-(B)Fd. nail WIT: (6)C M-33 West 3.5'	Frederick King Oct. 8, 1987 Liber 4, page 205 Mon.-(D)Fd. I & C WIT: (7)Fd. (12)Conc. R.O.W. marker West 55.50'
George Henning Sept. 1958 Mon.-None given WIT: (3)Fence line West (4)C M-33 West 3.3'	Norm Caldwell Jan. 30, 1979 Liber 3, page 46 Mon.-(B) WIT: (5) & (6)	Clifford Lindgren Oct. 3, 1988 LCRC Liber 3, page 41 Mon.-(C)Fd. (E)Set 3/4" rerod with cap stamped "MDOT 14096" in mon. box WIT: Fd. 8, 9, 10 & 11
George Henning June 18, 1959 Mon.-None given WIT: (4)	Clifford Lindgren Jan. 14, 1987 LCRC Liber 3, page 9 Mon.-(C)Fd. surveyors tag #12018 on rod WIT: (7)C M-72 (M-33) West 5.5' (3) & (5) fd. (8)8" R.Pine S80°E 63.55' (9)T.Pole S35°E 78.66' (10)Fence post N85°W 57.11' (11)T.Pole N35°W 74.72'	
Norm Caldwell Oct. 29, 1974 Liber 2, page 30 Mon.-None given WIT: (5)Set 3/4" bar & cap East 46.1'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner. And is accepted as a careful and faithful reestablishment of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard Oscoda County cap on 5/8" bar in pav't box, 3.5' East of C M-33 & 72
 WIT: Nail & tag set SW side 6' above telephone pole S35°E 78.66' (R)
 Nail & tag set NW side 5' above fence post N85°W 57.11' (R)
 Nail & tag set N. side 9" R.Pine 5' above S80°E 63.55' (R)

APPROVED

County Remonumentation
 Peer Review Group

16 NOV 96



Signed by Marvin E. Myers Date Sept.

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

**SURVEY &
 REMONUMENTATION**

MAY 19 1997

COMMISSION