

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. R. <u>3</u> E.	<u>F-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>27</u> N. R. <u>3</u> E.	<u>8, 9, 15, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 4-26 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 4-26 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-3---Set corner by proportionate measurement between sec. corners, which was a slight adjustment of Hennings 1937 corner.
- 8-----Set by standard survey procedure for the subdivision of sections.
- 9-----Found 1/2" pipe as previously established in local survey.
- 15-----Set by standard survey procedure for the subdivision of sections.
- 16-----Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3	Code 8	Code 9
DNR MOn. & Red Top Post	2½' of 1" pipe & redtop post	Fd. 1/2" pipe. Set Redtop post
Tw 4" Maples East 20.5'	9" J. Pine S 13 E 63.4'	4" W. Pine S 7W 10.3
7" Maple N16E 15.0'	Pk nail S side fn post	6" W. Pine S35W 28.9'
1" R. Pine N77W 10.2'	N 84 E 7.6'	10" R. Oak S62W 11.9'

Code 15	
2½' of 1" pipe & redtop post	
7" R. Pine S55 E 18.4'	
18" R. Pine N53 E 33.3'	

Code 16	
2½' of 1" pipe & redtop post	
8" Maple N 3W 13.6'	
10" Oak S85W 6.0'	


SIGNED BY Kenneth J. Ostling DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_