

SURVEY & REMONUMENTATION

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oscoda Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 27N R 2E M - 10
T 27N R 3E A - 10 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

26 NOV 96 3:22 P.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Marvin E. Myers, in a field survey on JUNE 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Lewis Clason May 1839 Norm Caldwell Mar. 21, 1980 Clifford Lindgren Oct. 3, 1988
Mon.-(A)Set post LCRC Liber 1, page 250 LCRC Liber 3, page 39
WIT: (1)24" Y.Birch S60½°W 37 lks. Mon.-(B) Mon.-(B) prior to construction
(2)24" Maple N46°W 68 lks. WIT: 3, 4, 5 & 6 (C)Reset ½" rod with cap stamped "MDOT 14098" in mon. box
Norm Caldwell Mar. 21, 1980 WIT: (7)P.Pole N45°E 61.74
Liber 3, page 222 & 223 Mon.-(B)Fd. bar & cap (8)P.Pole S28°E 95.50
WIT: (3)Fence corner West 51.15' (9)Fence cor. West 51.57'
(4)Fence post N45°W 68.0' (10)5" Elm N35°W 83.23'
(5)R.O.W. mon. East 50.0'
(6)Painted C_L M-33 East 3.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" bar in pavement box.
And is accepted as a careful and faithful reestablishment of the position of the original corner
Corner in common to T27N, R2E and T27N, R3E

APPROVED
County Remonumentation
Peer Review Group

*NGC
16 NOV 96*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced ½" Bar with standard Oscoda County Monument in pav't box
WIT: Fd. (9) MDOT nail & tag S. side (nail & tag on face also)
Fd. (8) MDOT nail & tag W. side P. Pole
Fd. (7) MDOT nail & tag S. side P. Pole
Fd. (6)
Fd. (5)
Fd. (3)
Fd. (4)



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date _____