

NOV 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION OSCODA

Liber 4 Pg 30

Table with columns: Located In: (County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
OSCODA COUNTY
FILED
15 OCT 98 2:56 P.M.
PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat APPROVED
5. Private Claims

County Remonumentation Peer Review Group

I, Frederick J. King, in a field survey on April 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A black dot is located at row 7, column C.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-7 - CORNER COMMON TO SECTIONS 17, 18, 19 and 20

- List of survey events from 1839 to 1998, including descriptions of monuments, bearings, distances, and references to previous surveys and records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-7 - CORNER COMMON TO SECTIONS 17, 18, 19 and 20
FOUND REC 1/2" IRON & ID CAP #14098 IN MONUMENT BOX + 10.7' NORTH OF C.L. OF E-W B.T. ROAD (M-33/72)
N.55*E- 35.83'- Fnd PK Spk In Curb Jnt (ID Cap Gone) + S.15*E.- 59.57'- Fnd PK Spk In Curb Jnt (ID Cap Gone)
S.35*W.- 50.82'- Fnd PK Spk In Curb Jnt (ID Cap Gone) + N.25*W.- 36.16'- Fnd PK Spk In Curb Jnt (ID Cap Gone)
NOTE: All above Witnesses Rec. in Bk. 3, Pg. 43)
THIS CORNER WAS APPROVED BY THE OSCODA COUNTY PEER REVIEW, ON JULY 10, 1998, AS A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-7 - CORNER COMMON TO SECTIONS 17, 18, 19 and 20
PLACED 5/8" IRON AND OSCODA COUNTY RE-MON CAP @ POSITION OF 1/2" IRON FOUND + IN MONUMENT BOX
Corner Is 10.7' North of C.L. of E-W B.T. Road (M-33/72)
N.55*E.- 35.83'- Re-Set PK Spk & ID Cap In Conc Curb + S.15*E.- 59.57'- Re-Set PK Spk & ID Cap In Conc Curb
S.35*W.- 50.82'- Re-Set PK Spk & ID Cap In Conc Curb + N.25*W.- 36.16'- Re-Set PK Spk & ID Cap In Conc Curb

Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date July 10, 1998

