

**SURVEY &
REMONUMENTATION**

OCT 08 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 Page 170

For corners in

COMMISSION

| | | |
|---------------------------------------|-------------|---------------|
| <u>Oscoda</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T27N R3E | C-10 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

STATE OF MICHIGAN
OSCODA COUNTY
FILED
29 AUG 97 8:57 A.M.
PATSY J. PETERS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, ^{P.S.} in a field survey on April 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|---|---|
| GLO - 1839 L. Clason, D.S. Mon - Post Wit: 6" Fir S34°W 23 Lks 14" W. Pine N35°E 6 Lks | Aug 28 1968 N. Caldwell, P.S. # 12018 Mon - Set 1/2x18" bar & Cap Wit: 6"x6" Concrete Mon N65°W 31.5 Telephone Pole N40°W 44.0 P. Pole S85°E 41.3 |
| Sept 28, 1888 J. Randall, Co. Surveyor Mon - Set Post Wit - not given | L.3, P. 388 F. King, P.S. #25852 June-27-1983 Mon - Found 1/2" bar Wit- Not given |
| Sept 19, 1916 C.O. Seeley, Co. Surveyor Mon - Found Old Stake Set a 2"x4' Casing Wit: New Bearing Monument of Cement 6"x6" with Iron Core N68 1/2°W 47 3/4 Lks | L. 194 P. 6900 L. Beauregard, P.S. # 18654 Sept-28-94 Mon - Found existing bar & cap by Caldwell Wit: 1/2" bar and cap East 33.0 |

APPROVED
County Remonumentation
Peer Review
APPROVED
County Remonumentation
Peer Review Group
NCC/12 AUG 97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR AND CAP for corner; found 6"x6" concrete monument N65°W 31.55; found 1/2" bar & cap S82°E 33.00; found 1/2" bar and cap N82°W 33.00; found P. Pole S83°E 41.3. Accepted 1/2" bar and cap as the best available evidence of the position of the Original Corner and replaced 1/2" bar with 5/8"x30' rebar with Standard Oscoda Co. Cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 common to Sections 29 & 30, T27N, R34E
Mon - Standard Oscoda County Monument in centerline N-S gravel road.
Wit: PK nail in West Side Power Pole N16°E 318.28
Pk nail in W. Face P. Pole S02°E 281.93
1/2" bar S82°E 33.00
1/2" bar N82°W 33.00

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date July 31, 1997

