

SURVEY & REMONUMENTATION

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 Page 177

For corners in

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T27N R3E	F-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling In Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
OSCODA COUNTY
FILED

29 AUG 97 9:04 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, P.S., in a field survey on June 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

A. Description of original monument and accessories and/or subsequent restoration:
 GLO - Oct 1839 L. Clason
 Mon - Post
 Wit: 8" Aspen N47°E 9 Lks
 14" Birch S48°W 20 Lks
 L3, P 100 Caldwell, P.S. #12018 July 20, 1979
 Mon - Placed Standard County Corner
 Wit: 8" R. Pine S50°E 20.3
 18" W. Pine S20°W 9.3
 3" R. Pine N70°E 33.3
 Fence corner North 0.5

LCRC L. 1, P. 228 N. Caldwell, P.S. #12018 Sept 27, 1979
 18" W. Pine S20°W 9.3
 3" R. Pine N70°E 33.3
 Fence corner North 0.5


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Standard Oscoda County Monument; found the following accessories, 8" R. Pine stump S50°E 20.3; found blaze in face 6" R. Pine N54°E 33.3; found blaze in face of 27" W. Pine S28°W 8.96; Found fence post North 0.5 Accepted as a careful and faithful establishment of the Position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1/4 common to Sections 28, & 33, T27N, R3E
 Mon - Standard Oscoda County Monument
 Wit: Nail in SE side 27" W. Pine S28°W 9.90
 Nail in E. side 22" W. Pine N06°W 34.80
 Nail in SE side 6" R. Pine N54°E 20.45
 Nail in NE side 4" Spruce S63°E 15.60
 Fence post North 0.5

APPROVED

County Remonumentation
Peer Review Group

NCC/12 AUG 97



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date *July 31, 1997*