

SURVEY & REMONUMENTATION

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 4 Page 187

For corners in

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T27N R3E	G-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
OSCODA COUNTY
FILED
29 AUG 97 9:14 A.M.
PATSY J. PETERS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, P.S., in a field survey on June 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:
 GLO - Oct 1839 L. Clason, D.S. LCRC L 1, P 230 Caldwell, P.S. #12018 7-20-1979
 Mon - Post Mon - Found no evidence of GLO or Seeley's
 Wit: 6" Spruce Pine S53°W 6 Lks Corner Set Standard Co. Corner by single proportion.
 4" Spruce Pine N51°E 11 Lks Wit: 18" Oak S25°W 24.0
 22" Maple Tw. Oak N65°W 28.60
 June 15., 1916 C.O. Seeley, Co. Surveyor 6" Maple S20°E 27.2
 Mon- Set 2" Pipe with Cedar stake 5" Maple N50°E 38.3
 Wit: 6" Oak N57°W 41 Lks.

APPROVED
County Remonumentation
Peer Review Group
NCC/12AUG97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Standard Oscoda Co. Monument; Found blazed 6" Maple S20°E 27.2; found blazed 5" Maple N50°E 38.3; found blaze & tag in 22" Tw. Oak Stump N65°W 28.6 Accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 ¼ corner common to Sections 33 & 34, T27N, R3E
Mon - Standard Oscoda County Monument
 Wit: Nail in NE side N65°E 6" Maple 38.57
 Nail in SE side S59°E 8" Cedar 32.41
 Nail in SW side S20°E 6" Maple 27.45
 Nail in N side N83°W 10" Poplar 34.58



Signed by *Marvin E. Myers*
 Surveyor's Michigan License No. 31600

Date *July 31, 1997*