

**SURVEY &
REMONUMENTATION**

OCT 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Liber 4 Page 179

For corners in

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T27N R3E	H-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
OSCODA COUNTY
FILED
29 AUG 97 9:06 A.M.
PATSY J. PETERS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, ^{P.S.} in a field survey on June 24, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

- A. Description of original monument and accessories and/or subsequent restoration.
- | | |
|---|---|
| GLO- Oct 1839 L. Clason, D.S.
Mon- Post
Wit- 18" Hemlock N32°E 28 Lks
8" Birch S30°W 10½ Lks | L3. P. 100 Caldwell, P.S. #18012 July 20, 1979
Mon - Placed Standard County Corner by S. P.
Wit- 20" R. Oak N75°W 10.7
22" R. Oak S35°W 33.2
8" Maple N10°W 27.35 |
| LCRC L. 1, P. 228 Caldwell, P.S. 9-27-1979
Mon- Placed Standard County Corner by S.P.
Wit- 20" R. Oak N75°W 10.7
22" R. Oak S35°W 33.2
8" Maple N10°W 27.35 | L. 4, P. 408 L. Beauregard, P.S. #18654 Oct 4, 1989
Mon- Existing Std. Co. Cor.
Wit- No new references marked |

APPROVED

County Remonumentation
Peer Review Group

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found existing Oscoda Co. Mon. With accessories recorded in L3, P. 100 in line with fence going North & West. Accepted Standard Oscoda County monument as a careful and faithful establishment of the position of the corner.

NCC/12 AUG 97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

¼ common to Sections 27, & 34, T27N, R3E
Mon - Standard Oscoda County Monument.
Wit: Spike in East side of 10" Maple N10°W 27.35
Set Spike in SE side of 18" R. Oak (with old blaze on face) N75°W 11.04
Spike in SE side 15" R. Oak S02°E 14.10
Spike in SE side 15" Poplar N61°E 4.75

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date *July 31, 1997*