

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

For corners in

OSCODA (County)	Located In: COMINS TWP.	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>3E</u>	<u>L-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

3 OCT 97 12:45 P.M.

PATSY J. PETERS  
REGISTER OF NEEDS

Liber 4 pg 233

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, FREDERICK J. KING, in a field survey on July 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13 - SOUTH 1/4 CORNER OF SECTION 36

May 1839 - Original Post set by L. Clason, D.S. - N68°E - 40 lks (26.40') - 11" Pine - N21°W - 19 lks (12.54') - 12" Pine Pg. 85

Sept 1930- GLO ReSurvey by G.R. Veal - Set by Prop Dist - No Original Evidence Found - Set 6"x24" Conc Mon & Brass Cap  
On File @ Reg of Deeds Pg. 20  
Cor L-1 (26-3) is 3.30' East  
N57 1/4°E - 187 lks (123.42') - 14" B. Oak  
N08 1/2°W - 47 lks (31.02') - 5" B. Oak

No Act 132 Found Recorded for this Corner  
No Act 74 Found Recorded for this Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 - SOUTH 1/4 CORNER OF SECTION 36

FOUND GLO CONC MONUMENT & BRASS CAP with USFS Post Alongside  
EAST - 15.2' - Fence Corner Post - Fence to East & North  
EAST - 3.41' - Found GLO Conc Mon & Brass Cap @ Corner L-1 (26-3)

**APPROVED**  
County Remonumentation  
Peer Review Group  
MCC  
30 SEPT 97

This Corner Approved by County Peer Review on July 11, 1997, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 - SOUTH 1/4 CORNER OF SECTION 36

GLO MONUMENT & BRASS CAP WITH Iron & USFS Red Top Post alongside 15' W of fence to North  
N25°E - 42.16' - Set S&T on W side of 15" Oak (Fnd Blz)  
S80°E - 5.60' - Set S&T on S side of Fence Corner Post  
S80°E - 21.82' - Set S&T on S side of 8" Maple ( Fnd Blz)  
S25°E - 5.89' - Set S&T on W side of 10" Oak (Fnd Blz)  
N55°W - 19.07' - Set S&T on S side of 10" Oak (Fnd Spk)  
EAST - 3.41'(R-3.30' G. Veal) GLO Mon 7 Brass Cap @ Cor L-1 (T26N-R3E)

Signed by Frederick J. King  
Surveyor's Michigan License No. 25852

Date Sept. 25, 1997