

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Oscoda</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 3E</u>	<u>M-2</u> ✓
	Sec. <u>T 27N R 4E</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 4 pg 291

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED

24 SEP 98 11:14 A.M.

PATSY J. PETERS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File  
 Number

I, Marvin E. Myers, in a field survey on 2 February, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
 May 1839  
 Lewis Clason D.S.  
 Mon: Post  
 Wit: 20" Hemlock S34°W 20 links  
 24" Hemlock N19°W 16 links

Norman C. Caldwell, R.L.S. Aug 22, 1966  
 (unrecorded Harry Dew survey)

Norman C. Caldwell, R.L.S. #12018 May 10, 1973  
 (Unrecorded Dwight Handrich Survey  
 Mon - Found record 3/4" bar and replaced with  
 Standard Oscoda County Corner Monument  
 Wit: Telephone Marker Post S80°W 27.5  
 P. Pole N45°W 79.8  
 18" Balsam N25°W 104.9

Larry G. Beauregard L.S. #18654 L3, P. 390 Aug 31, 1983  
 Mon: Existing Standard County Corner  
 Wit: Telephone Marker Post S80°W 27.5'  
 Power Pole N45°W 79.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Standard County Corner in centerline of North, South Road and centerline Road to East.  
 Found Power Pole N53°W 79.89'  
 Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 Cor. Sec. 1, T27N, R3E and Sec. 6, T27N, R4E  
 Mon: Standard County Corner monument in place.  
 Wit: Set Spike in South Side 16" White Pine S68°E 69.28'  
 Set Spike in South Side 13" Balsam N61°E 60.65'  
 Set Spike in South side Power Pole N53°W 79.89'  
 Set Spike in North side 8" Balsam N90°W 73.68'

**APPROVED**

County Remonumentation  
 Peer Review Group

*NCC 4 SEPT 98*



Signed by *Marvin E. Myers*  
 Surveyor's Michigan License No. 31600

Date August 25, 1998

SURVEY &  
 REMONUMENTATION

NOV 03 1998

SECTION