

**SURVEY &  
REMONUMENTATION**

NOV 03 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

<u>Oscoda</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. <u>T 27NR 3E</u>	<u>M-7</u>
	Sec. <u>T 27NR 4E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Liber 4pg 29*

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

24 SEP 98 11:19 A.M.

PATSY J. PETERS  
REGISTER OF DEEDS  
Register of Deeds Stamp & File  
Number

I, Marvin E. Myers, in a field survey on 19 February, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
May 1839  
Lewis Clason D.S.  
Mon: Post  
Wit: 30" Hd Maple S51°W 56 links  
2 0" Hd Maple N41 1/2°W 12 links

Edward P. Albertson, County Surveyor  
Minutes of Survey Pg 176, December 1900  
Mon: Stake In Ground  
Wit: 16" Beech S88°W 63 links  
14" Beech N68°E 78 links

Norman C. Caldwell R.L.S.#12018  
October 16, 1972 Liber 1, Page 256 - 258  
LCRC Liber 1, Page 190  
Mon: Found record iron in Mon. box 9.66'  
N. of centerline of M-72  
Wit: No new references marked

Clifford C. Lindgren R.L.S. #14098 M.D.O.T  
September 15, 1988 LCRC Liber 3 Page 25  
Mon: Found 5/8" rerod in monument box 9.7' North of M-72 centerline.  
Wit: Power Pole N08°E 65.63'  
10" Maple N33°E 99.62'  
Face of R.O.W. marker S05°W 84.68'  
12" Twin Maple S52°W 91.50'

F. King, PS #25852 Aug 1, 1987  
Mon - Fnd. 1" Bar in Mon Box  
Wit: 9.66 N. of centerline M-72

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 5/8" rerod in monument box 9.7' North of M-72 centerline in line with fence line North.

Wit: Found Power Pole with spike East face N08°E 65.63'  
Found 10" Maple with nail & tag East face N33°E 99.62'  
Found Face of R.O.W. marker S05°W 84.68'  
Found 12" Twin Maple with nail & tag NW face S52°W 91.50'

Tried to obtain MDOT data, received project field notes, August 17, 1998, which were incomplete and may have been miss-filed.  
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Sec. Cor. 13 & 24, T27N, R3E and 18 & 19 T27N, R4E  
Mon- 5/8" rerod placed Standard Oscoda County Cap on 5/8" rerod in monument box  
Wit: Power Pole with spike East face N08°E 65.63'  
10" Maple with nail & tag East face N33°E 99.62'  
Face of R.O.W. marker S05°W 84.68'  
12" Twin Maple with nail & tag NW face S52°W 91.50'

**APPROVED**

County Remonumentation  
Peer Review Group

*NCC  
4 SEPT 98*

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date August 23, 1998

