

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Liber 4 Pg. 8

For corners in

Oscoda

(County)

Located In:

Corner Code #

- |                                    |   |            |   |           |            |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>27N</u> | R | <u>4E</u> | <u>G-7</u> |
|                                    | T |            | R |           |            |
|                                    | T |            | R |           |            |
|                                    | T |            | R |           |            |
| 2. Property Controlling in Section | S |            | T | R         |            |
|                                    | S |            | T | R         |            |
| 3. Miscellaneous Property in Sec.  | S |            | T | R         |            |
|                                    | S |            | T | R         |            |

STATE OF MICHIGAN  
 OSCODA COUNTY  
 FILED

2 AUG 95 9:42 A.M.

PATSY J. PETERS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Babbitt, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-7; Thomas Pattison, 1840, wood post. B.Ts; Spr. Pine 14 - N45E - 41 Lks., Do 6 - S39W - 34 Lks.  
George D. Henning, 1953, Set 1" pipe and Oak post.  
 N.B.Ts: 10" B. Oak - S42E - 28.0', 8" B. Oak - S45W - 41.6', 8" B. Cherry - N44W - 39.6'  
Robert A. Griffin, Dec. 1961, Found 1"x 30" iron pipe and two bearing trees used by both George Henning and the Mich. State Hwy. Dept. Replaced the 1" pipe with a round re-inforced concrete post 6" in diameter with a 3" U.S.F.S. brass cap. N.B.Ts; 10" B. Cherry - N79E - 8' 15" Black Oak - S42E - 28.57', 8" B. Cherry - N44W - 39.67', Spike in P.P. - S53W - 35.23'  
Norman C. Caldwell, 1970, Found U.S.F.S. concrete monument and marker post 50' West of Camp Barakel access road. N.B.Ts; 10" Cherry - N79E - 82.0', 15" Oak - S42E - 28.6' 8" Cherry - N04W - 39.7', Power Pole - S53W - 35.2'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-7; Found U.S.F.S. concrete monument and marker post. The Oak NBT marked by Griffin and used by Caldwell is gone. The two cherry NBTs are in place but in very poor condition. The Power pole is in place still bearing Griffin's spike and RLS tag. This monument is accepted as being a careful and faithful reestablishment of the position of the original corner.

**APPROVED**

County Remonumentation  
 Peer Review Group

31 ~~APR~~ 95  
 JULY

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-7; Left U.S.F.S. concrete monument in place and marked new N.B.Ts;  
 4" N. Pine - S63E - 7.88'  
 11" N. Pine - S24W - 9.77'  
 spike with RLS 13584 tag in side of power pole - S60W - 35.24'  
 4" Balsam - N48W - 5.09'

All bearings shown are actual compass readings and measurements are to 3" spikes with plastic tags in the side of each bearing tree at the top of the root crown.

Signed by David B. Babbitt

Date Sept. 26, 1994

Surveyor's Michigan License No. 21558