

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <input checked="" type="radio"/> R. <u>1</u> E. <input checked="" type="radio"/>	A-5; B-5; C-5; C-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. <input type="radio"/> S. <input type="radio"/> R. _____ E. <input type="radio"/> W. <input type="radio"/>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. <input type="radio"/> S. <input type="radio"/> R. _____ E. <input type="radio"/> W. <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 14, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- A-5 Found Consumers Power Co. "T" iron at corner as established in previous survey.
- B-5 Set corner by proportionate measurement between section corners.
- C-5 Replaced Consumers Power "T" iron with DNR monument; corner previously of record in early surveys.
- C-6 Set corner by proportionate measurement between section corners. No previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5	B-5	C-5
Set DNR monument & red-top post	Set DNR mon. & red-top post	Set DNR mon. & red-top post
6" J. Pine S70°E 40.7	5" J. Pine S50°E 8.7	8" W. Oak S60°W 27.9
6" J. Pine S03°W 26.0	9" J. Pine S40°W 33.3	4" Maple S25°E 14.9
	C-6	
	Set DNR mon. & red-top post	
	7" Birch S70°W 25.5	
	10" J. Pine S50°E 3.0	

SIGNED BY *Kenneth J. Ostling* DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_