

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N. R. 1 E.


Oscoda COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 32 - 33 on south boundary of township

CORNER MONUMENT Left 1 1/4" pipe in place

DATE MONUMENT PLACED AND WITNESSED August 24, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" B. Oak N 24 1/2 E 127.3'

Old NBT 24" R. Pine N 56 1/2 W 90.1'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in Section 32. Found 1 1/4" pipe at corner as previously established by Randall from U.S. B.T.s and remarked by C. O. Seeley in 1915. Seeley's NBT still in place. Fence goes south from this corner, but it should be 78 links west.

Closing corner for Sections 4 - 5, T27NR1E is 78 links west.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostberg
REGISTERED LAND SURVEYOR

DATE September 5, 1962