

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 1 E.


Oscoda COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28 - 29 - 32 - 33

CORNER MONUMENT Set 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED August 24, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" B. Oak S 21 W 18.5'

8" J. Pine S 53 E 54.1'

AND

7" J. Pine N 46 E 41.1'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 32. Found a 12" rasp in place at corner as established in early 1900s by County Surveyor Seeley. His NBTs in place NE. Falls in center of E - W road, about in line with fence north.

SURVEYOR'S SEAL

SIGNED *Kenneth Ostling* DATE September 4, 1962
REGISTERED LAND SURVEYOR