

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 1 E.


Oscoda COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29 - 30 - 31 - 32

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 27, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" J. Pine N 45 W 14.5'

7" J. Pine S 24½ W 15.9'

AND

7" J. Pine S 40½ E 17.3'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 32. Found very old stake bottom by excavation in general area prescribed by old NBTs SW and N'ly, which are both down but identifiable. Probably set about the same time as others in this area, since it was noted in a Department survey in 1938.

SURVEYOR'S SEAL

SIGNED Kenneth Postley DATE September 5, 1962
REGISTERED LAND SURVEYOR