

1993

OSCODA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 3 Pg 151

COMMISSION

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
At 11:58 o'clock A M
Date 12-6 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on Nov 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Consumers Power Co. 1967
Mon. - Set "T" Iron
WIT: Nail & Blaze 5" J.Pine NW 24.57'
Nail & Blaze 5" J.Pine SE 45.96'
Nail & Blaze 5" Oak SW 33.45'
Nail & Blaze 10" Oak NE 105.41'

Walker 1992
Mon.

L.1, pg. 518

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron and accessories of record verified location by measurement to corners and accessories of recorded. Replaced "T" iron with 24" Oscoda County Monument set 0.5 feet below road surface, accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument- 24" Oscoda County Monument stamped top 31600 T28N, R1E
Witness: All Original witness given in part "A" above were found.
Pk nail in NW face 8" Black Oak N38°E 103.66'
PK nail in N. face 11" Red(Norway) Pine S52°E 70.50'
PK nail in SE face 12" Black Oak S47°W 33.93'
PK nail in NE face 4" J. Pine N64°W 41.18'
2" pipe N06°E 25.87 (Origin Unknown)



Signed by Marvin E. Myers

Date Nov 11, 1993

Surveyor's Michigan License No. 31600
Date approved Oct 25, 1993 Oscoda County Peer Group