

1993

OSCODA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OSCODA COMMISSION

Liber 3 Pg 152

Oscoda (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>28N</u> , R <u>1E</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**FILED**  
At 11:59 o'clock A M  
Date 12-6 1993  
Clerk/Register of Deeds  
Oscoda County, Michigan  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on Nov 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Dec. 1839 Coon Mon-Post Wit: 36" W. Pine N60°E 17 lks. 4" Aspen S20°E 6 lks.	DNR-May 1953 Mon- Found Stake verified by measurement to Stream South & Swamp West. WIT: 10" Balsam S55°W 102 lks.
Consumers Power Co. Oct. 1967 Mon- Set "T" iron Wit: none	Walker Surveys Feb. 1992 Mon- "T" iron. Wit: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron verified location by measurement to accessories and corners of record accepted as the best available evidence of the reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument-Set 24" Oscoda County Monument over top of "T" iron (now inside of monument)  
Witnesses: PK nail SW face 6" Poplar S62°E 8.84'  
PK nail in S. face 6" Poplar N36°W 12.84'  
PK nail in W. face 5" Poplar S40°W 5.46'  
PK nail in E. face 7" Poplar N42°E 17.49'



Signed by Marvin E. Myers Date Nov 11, 1993

Surveyor's Michigan License No. 31600  
Date approved Oct 25, 1993 Oscoda County Peer Group