

1899

OSCODA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA COUNTY

| Oscoda (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>A-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Liber 3 Pg 153

FILED

At 12:00 o'clock PM
Date 12-6 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on Nov 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO did not set a Monument

Consumers Power Company Oct 1967
Mon- None set

Farrier Surveying Oct 1993
Mon- none Set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1 1/2" pipe (may have by set by Marcus Schaaf) pipe is 0.84 East and 1.80 North of our computed position. This pipe is 73.92 feet South of a 1 1/2" pipe with 12" by 6" square concrete base (typical Schaaf monument) and accept as the best available evidence of the reestablishment of the Original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon- set standard Oscoda County monument replacing 1 1/2" pipe.
- Wit- PK nail in N. side 4" Red Pine (Norway) N58°E 17.22
- PK nail in SW side 3" Poplar S70°E 9.94
- PK nail in N. side 3" Poplar N87°W 12.57
- PK nail in W. side 11" Red Pine (Norway) 13.18



Signed by Marvin E. Myers Date DEC 6, 1993
Surveyor's Michigan License No. 31600
Date approved November 12, 1993 Oscoda County Peer Group